

BID FORM

To: United Keetoowah Band of Cherokee Indians in Oklahoma
Housing Department
Attention: Nicole O'Kelly

Client: **#1189** -
Stilwell, Ok -

I, the undersigned contractor, have inspected the above listed property of the client and understand the extent and character of the work to be completed as described in the scope of work as provided by the UKB Housing Department. In no event will a failure to inspect the site constitute grounds for a claim after contract award.

I propose to furnish all labor, materials, and equipment necessary to accomplish the work, as listed in the documents, on the client's property listed above for the sum of: \$_____.

(_____ Dollars)
(Be sure to write out the dollar amount)

I agree to commence the work once the Notice to Proceed is received. I agree to complete the work within the timeframe stated in the Notice to Proceed.

Company Name

Signature

Title

THIS BID MUST HAVE A BREAKDOWN OF MATERIALS AND LABOR:

Materials: _____

Labor Expense: _____

WorkWrite-Up and Bid Document/By Area

#1189
Stilwell, Ok

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date:

Area	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<u>BATHROOM #1</u>				
1	Vinyl Floor Tile. New vinyl floor tile/12" x 12" x 1/8".	Div. #9.L	72SF	<div style="border: 2px solid black; width: 100%; height: 40px;"></div>
<u>BEDROOM #1</u>				
2	Window/Replace/Vinyl/Thermopane/Low-E. Replace window with new Solid Vinyl window/Single hung. Use Am. Craftsman Series 2160-Vinyl or written approved equal. Include frame, sill, sash, trim, hardware, screen, repair & paint of int. and ext. surfaces. One in this area and two in different area	Div. #8.G	3Ea	<div style="border: 2px solid black; width: 100%; height: 40px;"></div>
<u>EXTERIOR</u>				
3	Septic Tank/Clean. Clean out septic tank.	Div. #11.A	1Ea	<div style="border: 2px solid black; width: 100%; height: 40px;"></div>
<u>INTERIOR</u>				
4	HVAC System/Service. Service complete HVAC system. See General Specifications.	Div. #12.M.	1Ea	<div style="border: 2px solid black; width: 100%; height: 40px;"></div>
<u>KITCHEN</u>				

<i>Area</i>	<i>Work Description /</i> <i>Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<u>KITCHEN</u>				
5		Div. #9.L	203 SF	
Vinyl Floor Tile. New vinyl floor tile/12" x 12" x 1/8".				
<u>LIVING ROOM #1</u>				
6		Div. #9.L	267 SF	
Vinyl Floor Tile. New vinyl floor tile/12" x 12" x 1/8".				
<u>LIVING ROOM #2</u>				
7		Div. #9.L	363 SF	
Vinyl Floor Tile. New vinyl floor tile/12" x 12" x 1/8".				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total: