

PROJECT SPECIFICATIONS

The United Keetoowah Band is seeking Proposals to remove and to replace the roof at the UKB Stilwell Strip Mall Building, 83981 Hwy 59 Stilwell, OK 74960. The Building is 150 ft long x 50 ft wide.

Statement of Vendor Qualifications Must Detail the Following:

1. A list of references
2. The installer must be a certified roofing contractor for the roofing system to be installed.

SUCCESSFUL BIDDER WILL INSTALL THE FOLLOWING PER MANUFACTURER'S RECOMMENDATIONS

1. Remove the existing roofing material down to the original decking on entire roofing substrate. All material removed from property must be properly and legally disposed of in land fill.
2. Install new insulation/underlay system to meet required county building code. The new insulation materials shall be fully adhered to the existing deck as per manufacturer and industry specifications.
3. 26 Gauge Metal
4. Ridge Cap
5. 100 Closures
6. 15 Ridge Capp
7. 100 25ft Sheets of Metal – Gray
8. 6,000 1 ½ Screws